

November 9, 1993

Mr. Dennis Boise Champlain Oil Company P.O. Box 2126 South Burlington, VT 05407

RE: Petroleum Contamination at Ballard's Store (VT DEC site #93-1409)

Dear Mr. Boise,

Enclosed is the report on the investigation of subsurface petroleum contamination at the above referenced location.

Please call me with any questions that you may have regarding the report.

Sincerely

usio 7. Recel

Staff Geologist

c: Chuck Schwer, VTDEC

SITE ASSESSMENT REPORT FOR BALLARD'S STORE HINESBURG, VERMONT VTDEC SITE #93-1409

NOVEMBER 9, 1993

Prepared for:

Champlain Oil Company South Burlington, VT

Prepared by:

Griffin International, Inc. 2B Dorset Lane Williston, VT 05495 (802) 879-7708

Griffin Project # 6934380

TABLE OF CONTENTS

	SECTION	PAGE
I.	INTRODUCTION	1 .
II.	SITE DESCRIPTION	1
III.	INVESTIGATIVE PROCEDURES A. Groundwater Sampling and Analysis B. Determination of Groundwater Flow Direction	1
IV.	RECEPTOR SURVEY	2
V.	RISK ASSESSMENT	2
VI.	CONCLUSIONS	3
VII.	RECOMMENDATIONS	4
APPI	ENDIX A: Site Location Map Detailed Site Map Groundwater Contour Map	
APPI	ENDIX B: Typical Monitoring Well Construction	
APPI	ENDIX C: Liquid Level Data	

APPENDIX D: Laboratory Results

I. INTRODUCTION

On June 19, 1993, Griffin International, Inc. (Griffin) inspected the removal of three underground storage tanks (UST) at Ballard's Store in Hinesburg. The old tanks and replacement tanks are owned by Champlain Oil Company (COCO). During the tank removal, subsurface petroleum contamination was detected. Approximately 60 cubic yards of this soil was removed, stockpiled on-site and encapsulated with polyurethane. Further investigations were requested by the Vermont Department of Environmental Conservation (VTDEC) to determine the extent and degree of subsurface contamination. Griffin submitted to the VTDEC a Cost Estimate and Work Plan to conduct a site assessment at Ballard's Store.

This plan was approved by the VTDEC Sites Management Section on August 9, 1993. Champlain Oil Company retained the services of Griffin to perform the site assessment per the approved Work Plan. This report details Griffin's investigation, including conclusions and recommendations.

II. SITE DESCRIPTION

The Ballard's Store site is located on Shelburne Falls Road, just west of the intersection with Route 116 (or Hinesburg Road) in Hinesburg. This area contains a mix of commercial, agricultural and residential properties. The topography of the site is generally flat. Drainage at the site flows to a swale located on the north and west perimeter of the area. Drainage flows westward in the swale before the swale bends and the flow becomes southerly.

The Ballard's store has its own drinking water supply well which also supplies the adjacent hardware store, bank, restaurant, dental office, and retail meat store, located to the north east of Ballard's. The well is under natural positive pressure, and water flows from the well head. The well is drilled into bedrock mapped as Winooski Dolomite on the Geologic Map of Vermont. The Dolomite is overlain by silt and clay.

III. INVESTIGATIVE PROCEDURES

To further define the extent and degree of subsurface contamination, Griffin collected water samples from an on-site supply well and four monitoring wells that were installed by COCO before and during the tank removal in June, 1993.

Griffin also surveyed the site to provide locations and elevations of major site features including buildings and monitoring wells. This data is plotted on the enclosed site maps in Appendix A and will be used to help define the present contamination and predict its impact on potential local receptors.

A. GROUNDWATER SAMPLING AND ANALYSIS

On June 18, 1993, Griffin collected a water sample from the supply well for the store. This sample was collected from the sink inside the Deli. Analysis of the water sample showed no detectable contaminants.

On August 24, 1993, Griffin discovered three of the monitoring wells at the site were either destroyed or paved over. Griffin collected water samples from the remaining monitoring wells MW1, MW3, MW4, and MW5, plus three quality control and quality assurance samples. The samples were collected using Griffin's sampling protocol and analyzed using EPA Method 602 which tests for benzene, toluene, ethylbenzene, and xylene (BTEX compounds) and methyl tertiary butyl ether (a gasoline additive). No contaminants were detected in MW1. The samples collected from MW3, MW4, and MW5 did contain elevated concentrations of benzene and MTBE above the Vermont Drinking Water Standards. The results of water quality analysis are summarized in Table 1 along with Vermont Drinking Water Standards. The laboratory results are included in Appendix D.

Duplicate, trip blank and equipment blank samples indicate that QA/QC (quality assurance and quality control) was maintained during sampling, transportation and analysis. The QA/QC test results are also included in this report.

B. GROUNDWATER DIRECTION AND GRADIENT

During the site visit on August 24, Griffin measured the depth to the water table in each well prior to sampling. The elevations are based on arbitrary datum by assigning an elevation of 100 feet to the top of the casing of MW1. These measurements are shown in the Liquid Level Data Summary in Appendix C. The data was used to construct a groundwater contour map (Appendix A.) The Groundwater Contour Map indicates groundwater apparently flows towards the east. The gradient is calculated to be 1.0 percent. This slight gradient and low estimated permeability likely result in a relatively slow rate of groundwater flow.

IV. RECEPTOR SURVEY

Griffin conducted a visual survey of the site in order to identify potential receptors of subsurface petroleum contamination. Potential receptors include the Ballard's Store, the supply well on the north side of the building, and the drainage swale, also on the north side of the building. This swale drains to a tributary which discharges to the LaPlatte River, about 1/2 mile southwest of the site.

V. RISK ASSESSMENT

Ballard's building does not appear to be at risk of petroleum contamination because of it's on-grade slab construction. Other buildings in the area are either up-gradient or too far away to likely be impacted. The water supply well has not been impacted by the contamination. This well is under positive pressure, and water flow is common from the well head. This suggests that surface water in the area would not recharge into the bedrock, therefor contamination of the bedrock is unlikely. The drainage swale did not show any evidence of petroleum contamination.

Table 1

Groundwater Quality Summary Ballard's Store Hinesburg, Vermont

Monitoring Well: MW-1

	Date of Sample Co	Vermont Drinking	
PARAMETER	8/24/93		Water Standard
Benzene	ND		5.0*
Chlorobenzene	ND		100**
1,2-DCB	ND		•
1,3-DCB	ND		-
1,4-DCB	ND		•
Ethylbenzene	ND		680**
Toluene	ND		2420**
Xylenes	ND		400**
Total BTEX	ND		
MTBE	ND		40**
BTEX+MTBE	NĐ		

Monitoring Well: MW-3

	Date o	f Sample Co	llection	Vermont Drinking
PARAMETER		8/24/93		Water Standard
Benzene	1	ND		5.0*
Chlorobenzene		ND		100**
1,2-DCB		ND	-	-
1,3-DCB		ND		-
1,4-DCB		ND		-
Ethylbenzene		ND		680**
Toluene		2.0		2420**
Xylenes		5.5		400**
Total BTEX		7.5		
MTBE		12400		40**
BTEX + MTBE		12407.5		

Monitoring Well: MW-4

	Date o	f Sample Co	llection	 Vermont Drinking	
PARAMETER		8/24/93		Water Standard	
Benzene	1	84.4		5.0*	
Chlorobenzene		ND		 100**	
1,2-DCB		ND		-	
1,3-DCB		ND		 -	
1,4-DCB		ND		 -	
Ethylbenzene	7	ND		680**	
Toluene		11.3		2420**	
Xylenes		13.6		400**	
Total BTEX		109.3			
MTBE		1470		40**	
BTEX + MTBE		1579.3			

All values reported in ug/L

ND - None Detected

TBQ - Trace, Below Quantitation Limits

^{* -} Maximum Contaminant Level

^{**-}Health Advisory Levels

Groundwater Quality Summary Ballard's Store Hinesburg, Vermont

Monitoring Well: MW-5

	Date o	Vermont Drinking			
PARAMETER		8/24/93			Water Standard
Benzene		17.1			5.0*
Chlorobenzene		ND			100**
1,2-DCB	:	ND			
1,3-DCB		ND			•
1,4-DCB		ND			•
Ethylbenzene		ND		1	680**
Toluene		7.7			2420**
Xylenes		7.0	·		400**
Total BTEX		31.8			
MTBE		2140			40**
BTEX+MTBE		2171.8			

All values reported in ug/L

ND - None Detected

TBQ - Trace, Below Quantitation Limits

* - Maximum Contaminant Level

**-Health Advisory Levels

Due to the groundwater flow direction away from these potential receptors, it is unlikely that they will be impacted by the contaminants.

VII. CONCLUSIONS

Based on our investigations, Griffin has reached the following conclusions:


- 1) During a routine UST replacement on June 14 and 15, contaminated soils were detected in the vicinity of the old tank pit. The source was attributed to a leak in the old piping from the tanks to the pumps. The replacement of the USTs, pumps and piping has removed the probable active sources of subsurface petroleum contamination.
- 2) Residual dissolved phase contamination is present in the groundwater as indicated by the results of the sample analyses. Some concentrations of petroleum compounds are above the Vermont Drinking Water Standards in three of the four wells that were sampled on August 24, 1993.
- 3) Water quality results indicate that contamination appears to be highest in the vicinity of the former USTs and slightly downgradient. However, MW1, located furthest downgradient, did not contain any petroleum contamination.
- 4) No free phase product was found at the site. VOC concentrations in the soils excavated during the removal of on-site USTs averaged 14.5 ppm with a peak detection of 70 ppm.
- 5) The potential receptors listed above do not appear to be at risk from the residual contaminants.
- 6) Removal of approximately 60 cubic yards of contaminated soils resulted in the removal of a significant portion of contamination.
- 7) Over time, the natural processes of dilution, volatilization and biodegradation should result in a reduction of contamination concentrations to below detectable limits.


RECOMMENDATIONS


- 1) Due to the concentrations of subsurface petroleum contamination, the groundwater flow direction, and the lack of significant risks to potential receptors, Griffin recommends monitoring the site to track the migration and reduction of the contamination. Presently we recommend resampling the same on-site monitoring wells on an annual basis and the supply well on a bi-annual basis and performing EPA Method 602 analyses of these samples to determine the concentrations of BTEX and MTBE. The supply well should be sampled again in December 1993, the monitoring wells should be sampled in August 1994. Once a downward trend in contamination concentrations is identified and the contaminant levels fall below the Vermont Drinking Water Enforcement Standards, we will recommend site closure.
- 2) Representative soil samples should be collected with a hand auger from the stockpile, now located on site, and screened with a PID on a bi-annual basis. The results of these inspections will assist in documenting the reduction of contamination over time. When the stockpiled soils are shown to contain VOC concentrations less than 5 ppm, we will recommend that they be used on site for backfill or returned to grade and seeded in accordance with state regulations.

APPENDIX A

Site Location Map Site Map Groundwater Contour Map







MONITORING WELL

⊕ FORMER MONITOR VELL

UNDERGROUND STORAGE TANK

GROUNDWATER CONTOUR LINE

JOB #: 6934380

BALLARD'S STORE					
HINESBUR	HINESBURG, VERMONT				
GROUNDWATER CONTOUR PLAN					
DATE:19/11/93	DWG.#:3 of 3	SCALE: 1'=60'	DRN.: SB	APP.: PM	

APPENDIX B

Typical Monitoring Well Construction

WELL NUMBER TYPICAL PROJECT Ballard's Store Site Sketch LOCATION Hinesburg, Vermont POWER COCATION DATE DRILLED 6/93 ____TOTAL DEPTH OF HOLE 13'_ DIAMETER__ N\A SCREEN DIA. 4" LENGTH 10' SLOT SIZE ____ CASING DIA. 4" LENGTH 3' TYPE sch 40 pvc DRILLING CO. T.L. Boise DRILLING METHOD Back Hoe DRILLER Tom Boise LOG BY P. MURRAY GRIFFIN INTERNATIONAL, INC DESCRIPTION/SOIL CLASSIFICATION DEPTH BLOWS PER WELL DEPTH NOTES 6" OF SPOON IN CONSTRUCTION (COLOR, TEXTURE, STRUCTURES) FEET FEET & PID READINGS -ROAD BOX LOCKING WELL CAP - 0 -- CONCRETE - 1 -2 - 2 ---WELL RISER N\A - 3 ⊢ 3 - 4 **–** -4. - 5 --- 5 -6-- 6 -BACKFILL Pea Stone backfill - 7 -- 8 -- 8 - 9 -- WELL SCREEN - 9 –10 **–**1 -10 --11 ---11 -12 -BOTTOM CAP -12 END OF EXPLORATION AT 13' -13 ---13 UNDISTURBED NATIVE SOIL -14 --15 --15 -–16 – -16 --17 --17 --18 -**-1**8 · -19 --19 --20 -20--21 --21 --22--22--23--23--24--24 -25--25

APPENDIX C

Liquid Level Data

Liquid Level Monitoring Data Ballard's Store Hinesburg, Vermont

Monitoring Date:8/24/93

				MOU	itoring Date:6/2	4) PO			
I		Тор				Specific		Corrected	Corrected
Well I.D.	Well	of Casing	Depth To	Depth To	Product	Gravity	Hydro	Depth	Water Table
ŀ	Depth	Elevation	Product	Water	Thickness	Of Product	Equivalent	To Water	Elevation
MW-1	NA	100.00	-	4.64	-	-	-	4.64	95.36
MW-2	NA	98.67	-	3.06	-	-	-	3.06	95.61
MW-3	NA	98.60		2.78	-	-	-	2.78	95.82
MW-4	NA	98.47	-	2.68	-	-	-	2.68	95.79
MW-5	NA	98.33	<u></u>	2.73	-	-	-	2.73	95.60
·									
l									
The state of the s						• • • • • • • • • • • • • • • • • • • •			
							-		
i			i ·						
· · · · · · · · · · · · · · · · · · ·				•					
			i	• • • • • • • • • • • • • • • • • • • •					Ĭ
		•					1		

NA -Not Available All Values Reported in feet

APPENDIX D

Laboratory Results

1993

Laboratory Services

32 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

REPORT OF LABORATORY ANALYSIS

CLIENT: Griffin International PROJECT NAME: Ballards

REPORT DATE: September 7, 1993 DATE SAMPLED: August 24, 1993 PROJECT CODE: GIBA1418

REF.#: 50,457 - 50,463

Enclosed please find the results of the analyses performed for the samples referenced on the attached chain of custody. Chain of custody indicated samples were preserved with HCl.

All samples were prepared and analyzed by requirements outlined in the referenced method and within the specified holding times. All instrumentation was calibrated with the appropriate frequency and verified by the requirements outlined in the referenced method. Blank contamination was not observed at levels affecting the analytical results.

Analytical method precision and accuracy was monitored by laboratory control standards which included matrix spike, duplicate and quality control analyses. These standards were determined to be within established laboratory method acceptance limits.

Individual sample performance was monitored by the addition of surrogate analytes to each sample. All surrogate recovery data was determined to be within laboratory QA/QC guidelines unless otherwise noted.

Reviewed by

Harry B. Locker, Ph.D. Laboratory Director

enclosures



32 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

LABORATORY REPORT

EPA METHOD 602 -- PURGEABLE AROMATICS

CLIENT: Griffin International PROJECT NAME: Ballards

REPORT DATE: September 7, 1993 DATE SAMPLED: August 24, 1993 DATE RECEIVED: August 24, 1993 ANALYSIS DATE: September 4, 1993 PROJECT CODE: GIBA1418

REF.#: 50,457

STATION: Trip Blank TIME SAMPLED: 7:30 SAMPLER: B. Schuyler

<u>Parameter</u>	Detection Limit (ug/L)	Concentration (ug/L)
Benzene	1	ND^1
Chlorobenzene	1	ND
1,2-Dichlorobenzene	1	ND
1,3-Dichlorobenzene	1	ND
1,4-Dichlorobenzene	1	ND
Ethylbenzene	1	ND
Toluene	1	ND
Xylenes	1	ND
MTBE	10	ND

Bromobenzene Surrogate Recovery: 105%

NUMBER OF UNIDENTIFIED PEAKS FOUND: 0

NOTES:

32 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

LABORATORY REPORT

EPA METHOD 602 ~ PURGEABLE AROMATICS

CLIENT: Griffin International

PROJECT NAME: Ballards REPORT DATE: September 7, 1993

DATE SAMPLED: August 24, 1993 DATE RECEIVED: August 24, 1993

ANALYSIS DATE: September 4, 1993

PROJECT CODE: GIBA1418

REF.#: 50,458

STATION: MW 1

TIME SAMPLED: 11:30 SAMPLER: B. Schuyler

Parameter	Detection Limit (ug/L)	Concentration (ug/L)
Benzene	1	ND¹
Chlorobenzene	1	ND
1,2-Dichlorobenzene	1	ND
1,3-Dichlorobenzene	1	ND
1,4-Dichlorobenzene	1	ND
Ethylbenzene	1	ND
Toluene	1	ND
Xylenes	1	ND
MTBE	10	ИD

Bromobenzene Surrogate Recovery: 110%

NUMBER OF UNIDENTIFIED PEAKS FOUND: 0

NOTES:

32 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

LABORATORY REPORT

EPA METHOD 602 -- PURGEABLE AROMATICS

CLIENT: Griffin International PROJECT NAME: Ballards

REPORT DATE: September 7, 1993 DATE SAMPLED: August 24, 1993 DATE RECEIVED: August 24, 1993

ANALYSIS DATE: September 4, 1993

PROJECT CODE: GIBA1418

REF.#: 50,459 STATION: MW 3

TIME SAMPLED: 11:45 SAMPLER: B. Schuyler

<u>Parameter</u>	Detection Limit (ug/L)	Concentration (ug/L)
Benzene	1	· MD1
Chlorobenzene	1	ND1
1,2-Dichlorobenzene	1	ND
1,3-Dichlorobenzene	4	ND
	1	ND
1,4-Dichlorobenzene	1	ND
Ethylbenzene	1	ND
Toluene	1	_
Xylenes	1	2.0
MTBE	1	5.5
WIIDE	10	12,400.

Bromobenzene Surrogate Recovery: 87%

NUMBER OF UNIDENTIFIED PEAKS FOUND: 8

NOTES:



32 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

LABORATORY REPORT

EPA METHOD 602 -- PURGEABLE AROMATICS

CLIENT: Griffin International

PROJECT NAME: Ballards

REPORT DATE: September 7, 1993 DATE SAMPLED: August 24, 1993

DATE RECEIVED: August 24, 1993 ANALYSIS DATE: September 7, 1993 PROJECT CODE: GIBA1418

REF.#: 50,460 STATION: MW 4

TIME SAMPLED: 12:00

SAMPLER: B. Schuyler

<u>Parameter</u>	Detection Limit (ug/L) ¹	Concentration (ug/L)
Benzene	5	84.4
Chlorobenzene	5	ND^2
1,2-Dichlorobenzene	5	ND
1,3-Dichlorobenzene	5	ND
1,4-Dichlorobenzene	5	ND
Ethylbenzene	5	ND
Toluene	5	11.3
Xylenes	5	13.6
MTBE	50	1,470.

Bromobenzene Surrogate Recovery: 108%

NUMBER OF UNIDENTIFIED PEAKS FOUND: 0

NOTES:

- 1 Detection limit raised due to high levels of contaminants. Sample run at 20% dilution.
- 2 None detected



32 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

LABORATORY REPORT

EPA METHOD 602 -- PURGEABLE AROMATICS

CLIENT: Griffin International PROJECT NAME: Ballards

REPORT DATE: September 7, 1993 DATE SAMPLED: August 24, 1993

DATE RECEIVED: August 24, 1993 ANALYSIS DATE: September 7, 1993 PROJECT CODE: GIBA1418

REF.#: 50,461 STATION: MW 5

TIME SAMPLED: 12:10 SAMPLER: B. Schuyler

<u>Parameter</u>	Detection Limit (ug/L)1	Concentration (ug/L)
Benzene Chlorobenzene 1,2-Dichlorobenzene 1,3-Dichlorobenzene 1,4-Dichlorobenzene Ethylbenzene Toluene Xylenes MTBE	5 5 5 5 5 5 5 5	17.1 ND ² ND ND ND ND 7.7 7.0 2,140.
		2,140.

Bromobenzene Surrogate Recovery: 120%

NUMBER OF UNIDENTIFIED PEAKS FOUND: 0

NOTES:

- 1 Detection limit raised due to high levels of contaminants. Sample run at 20% dilution.
- 2 None detected

[M-M3-1332 MI:2341] LKOU CUDIVE: 11



Laboratory Services

32 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

LABORATORY REPORT

EPA METHOD 602 - PURGEABLE AROMATICS

CLIENT: Griffin International PROJECT NAME: Ballards

REPORT DATE: September 7, 1993 DATE SAMPLED: August 24, 1993 DATE RECEIVED: August 24, 1993 ANALYSIS DATE: September 7, 1993 PROJECT CODE: GIBA1418

REF.#: 50,463

STATION: Equip. Blank TIME SAMPLED: 12:15 SAMPLER: B. Schuyler

<u>Parameter</u>	Detection Limit (ug/L)	Concentration (ug/L)
Benzene	1	ND¹
Chlorobenzene	1	ND
1,2-Dichlorobenzene	1	ND
1,3-Dichlorobenzene	I	ND
1,4-Dichlorobenzene	1	ND
Ethylbenzene	1	ND
Toluene	1	ND
Xylenes	1	ND
MTBE	10	ND

Bromobenzene Surrogate Recovery: 112%

NUMBER OF UNIDENTIFIED PEAKS FOUND: 0

NOTES:

ENDYNE, INC.

32 James Brown Drive Williston, Versiont 65495 (802) 879-4333

CHAIN-OF-CUSTODY RECORD

Endyne Project Number: Company: Contact Name/Phone H: Sampler Name: Bessel Sampler Name: Sampler Name: Bessel Sampler Name: Sampler Name: Bessel Sam	Site L	ocatio	ne: Ballards m: Hinesbur	9			Re	роги	ig Addr	ess: G c : { {	in				ng Address: Gr.				
Sample Location Mark R S Descripts Sample Container Fisch Remits Required Processation Rush	Endyr	ie Pro	ject Number: GL	BA	1418					Phone #:				Sami Phon	pler Name: 8 e < <- le #: - ½ 7 ½ - 7 7	a 5, h 08	uy la	: i"	
### ##################################						Ma	trix	G R	CO M	Date/Time	<u>} </u>	\$1500 SEC. 71 SEC.		Field Res	ulls/Remarks				Rush
11.30	50. J	51	Trie Blan	K	**************************************	Ha	0	<u>>≈••••</u>	1		-		1. (1.755.4.4.7.	<u> </u>	\$\$\$\$\$\$\$\\$\\$\\\\\\\\\\\\\\\\\\\\\\\\\\\	600	2	HCL	
1 2 3 3 4 4 5 5 5 5 5 5 5 5	504	56_	1 7				}			11:30		1				1			
12:10 12:1			MWZ																
12:10 12:1	£2.45	4	MWS								Ш.								
Relinguished by: Signature Received by: Signature Requested Analyses 1 pH 6 TKN 11 Total Solids 16 Mesalt (Specify) 21 EPA 624 26 EPA 8270 EN or Acid 2 Chloride 7 Total P 12 TSS 17 Coliforn (Specify) 22 EPA 625 EN or A 27 EPA 810(0,00020)	30.4	60							ļ								.		
Relinguished by: Signature Received by: Signature Received by: Signature Received by: Signature Received by: Signature Received by: Signature Received by: Signature Received by: Signature Received by: Signature Received by: Signature Requested Analyses 1 pH 6 TKN 11 Total Solids 16 Mesals (Specify) 21 EPA 624 26 EPA 8270 B/N or Acid 2 Chloride 7 Total P 12 TSS 17 Californ (Specify) 22 EPA 625 B/N or A 27 EPA 8010/8070	504	61	MW5		·			1			$\bot \bot$								
Relinguished by: Signature	500	162	1500 Dup. 0	171	v S"												,		
Relinguished by: Signature	<u> 5Ú I</u>	63	Equip. Bl.	ank		V		<u>\(\psi \) \(\psi \) \(\psi \)</u>		12:15	14					<u> </u>		Ψ	
Received by: Signature Date/Time									<u> </u>		-		<u> </u>				_	·	
Received by: Signature Date/Time							····				ļ						_		
Received by: Signature Date/Time						<u> </u>			ļ		ļ	ļ	<u> </u>						
Received by: Signature Date/Time		<u> </u>			3 /	1			<u> </u>			<u> </u>							
Requested Analyses	Relinguished by: Signature Been Paryly							Received by: Signature in M. leavers						Date/	time 8/24/9	}			`, j s-
i pH 6 TKN 11 Total Solids 16 Mostle (Specify) 21 EPA 624 26 EPA 8270 B/N or Acid 2 Chloride 7 Total P 12 TSS 17 Coliform (Specify) 22 EPA 625 B/N or A 27 EPA 8010/8020	Relinguished by: Signature						Red	Received by: Signature						Date/	l'ime				,
2 Chloride 7 Total P 12 TSS 17 Coliform (Specify) 22 EPA 625 B/N or A 27 EPA 8010/8020										Requested	Analy:	es							
	i	ρН		6	TKN		,	1	Foul Solid	•	16	Motals (Specify	;)	21		26	ļ		Acid
12 TDS 123 FPA 4881 28 FPA 4881 PGUPCB	2	Chlor	ride	7			1				17	Coliforn (Spec	ify)	22	EPA 625 B/N or A	27	ļ		

Н	•	₅ ,	9 - 9						<u> </u>		1	<u> </u>
I	2	Chloride	7	Total P	12	TSS	17	Caliform (Specify)	22	EPA 625 B/N or A	27	EPA 8010/8020
1	3	Аптинопія N	8	Total Diss. P	13	TDS	18	COD	23	EPA 418.1	28	EPA 8080 PervPCB
ı	4	Nitrito N	9	BOD,	14	Turbidity	19	BTEX	24	EPA 608 Pest/PCB		
ľ		Nitrate N	10	Alkalinity	15	Conductivity	20	EPA 601/602	25	EPA 8240		

29 TCLP (Specify: volatiles, semi-volatiles, metals, pesticides, herbicides)

30 Other (Specify):

32 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

REPORT OF LABORATORY ANALYSIS

CLIENT: Griffin International

PROJECT NAME: Ballard's REPORT DATE: June 21, 1993 DATE SAMPLED: June 18, 1993

PROJECT CODE: GIBL1993

REF.#: 47,774

Enclosed please find the results of the analyses performed for the samples referenced on the attached chain of custody. Chain of custody indicated samples were preserved with HCl.

All samples were prepared and analyzed by requirements outlined in the referenced method and within the specified holding times. All instrumentation was calibrated with the appropriate frequency and verified by the requirements outlined in the referenced method. Blank contamination was not observed at levels affecting the analytical results.

Analytical method precision and accuracy was monitored by laboratory control standards which included matrix spike, duplicate and quality control analyses. These standards were determined to be within established laboratory method acceptance limits.

Individual sample performance was monitored by the addition of surrogate analytes to each sample. All surrogate recovery data was determined to be within laboratory QA/QC guidelines unless otherwise noted.

Reviewed by,

Harry B. Locker, Ph.D. Laboratory Director

enclosures



32 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

LABORATORY REPORT

EPA METHOD 602 -- PURGEABLE AROMATICS

CLIENT: Griffin International PROJECT NAME: Ballard's

REPORT DATE: June 21, 1993 DATE SAMPLED: June 18, 1993 DATE RECEIVED: June 18, 1993 ANALYSIS DATE: June 18, 1993 PROJECT CODE: GIBL1993

REF.#: 47,774

STATION: Supply Well TIME SAMPLED: 9:25 SAMPLER: B. Schuyler

<u>Parameter</u>	Detection Limit (ug/L)	Concentration (ug/L)
Benzene	1	ND^1
Chlorobenzene	1	ND
1,2-Dichlorobenzene	1	ND
1,3-Dichlorobenzene	1	ND
1,4-Dichlorobenzene	1	ND
Ethylbenzene	1	ND
Toluene	1	ND
Xylenes	1	ND
MTBE	5	ND

Bromobenzene Surrogate Recovery: 103%

NUMBER OF UNIDENTIFIED PEAKS FOUND: 0

NOTES:

32 James Brown Drive Williston, Vermont 05495 CHAIN-OF-CUSTODY RECORD

48 Heek Rush 006340

(802	2) 879-4333	(7)	<i>()</i>)						·				
Site Location	ne: Ballards on: Hinesburg/VT		Reporti	ıg Addı	ress: G e i f	(, ,	1		Billing Address:	6-51			
Endyne Pro	ject Number: CIT BL 1 793		Compar Contact	y: Name/	Phone #: 279	r <i>F</i> ic	708		Sampler Name: 15 c c Phone #: 77	сь. 5сп - 70 9			
Lab#	Sample Location	Mate	ix R A B	C O M P	Date/Time	Sampl No.	e Containers Type/Size		Field Results/Remarks	Analysis Required	Sample Preservation	Rush	
49774	Supply Well	Ha	0 X		6-16 1.05	a	40m6			600	711 1	メ	
	Puplicate				L	1	V			ŭΣ	Ø.		
	<i>y</i>												
•	DO NA FUIL											-	
	Suglicate												
					!								
<u> </u>							· ·						
										<u> </u>			
· .					 								
				1]							
	,	//	7	1									
Relinguished b	Dy: Signature Blecco School	7	Received	bys- Sigm	sture \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	ا ک	haml	ris_	Date/Time 6/18/0	7 3		:50	
Relinguished b	py: Signature		Received by: Signature						Date/lime				

Requested Analyses

t	рН	6	TKN	11	Total Solids	16	Metals (Specify)	21	EPA 624	26	EPA 8270 B/N or Acid		
2	Chloride	7	Total P	12	TSS	17	Californ (Specify)	22	EPA 625 B/N or A	27	EPA 8010/8020		
3	Ammonia N	8	Total Diss. P	13	TDS	18	COD	23	EPA 418.1	28	EPA 8080 Past/PCB		
4	Nitrite N	9	BOD,	14	Turbidity	19	BTEX	24	EPA 608 Pest/PCB				
5	Nitrate N	10	A!kalinity	15	Conductivity	20	EPA 601/602	25	EPA 8240				
29	TCLP (Specify: volatiles, semi-volatiles, metals, pesticides, herbicides)												
30	Other (Specify):	Other (Specify):											